



Engineering Division

TOWN OF ARLINGTON
Department of Public Works
51 Grove Street
Arlington, Massachusetts 02476
Office (781) 316-3320 Fax (781) 316-3281

2020 GREEN INFRASTRUCTURE IMPROVEMENT PROJECT

BID #20-09

March 2, 2020

ADDENDUM #1

The Elevation data utilized on the BMP Sketches for Green Trenches and Tree Trenches should be updated as presented below for BMPs #1, 3, 4, 6, 7, 8, 9, 10, 11, 12.

Please note that the gutter inlet at each location will continue to be utilized as the individual datum (El.=0.00) for each BMP.

Original

Elevations

Gutter Inlet:	0.00
Gutter Outlet:	-0.25
Chamber Inlet:	-0.25
4" Invert Out #1:	-0.75
4" Trench Outlet #2:	-0.75
Chamber Bottom:	-1.25
Top of Stone:	-1.25
Top of Stone:	-0.75
4" Invert Perf. Pipe:	-1.25
Bottom Stone:	-3.75

Revised

Elevations

Gutter Inlet:	0.00
Gutter Outlet/Chamber Inlet:	-0.25
4" Invert Outlet #1:	-0.75
4" Invert Outlet #2:	-0.75
Chamber Bottom:	-1.25
Top of Stone:	-0.25
Bottom Stone:	-3.25